

SAFE HOME / LEADSAFE CHARLOTTE

CITY OF CHARLOTTE

HOUSING & NEIGHBORHOOD SERVICES

BID OPENING CERTIFICATION RECORD							
Date of Bid Walk: 12/4	Due Date:	12/13/18	HNS <u>/ 9</u>	-29			
Public Body Estimate							
Address	PBE Amount	PBE -15%	***************************************	+15%			
853 BELMONT	29,576	25,140	34	34,012			
			:				
,	Bid Re	esults					
Addresses	Bidder 1 Bidder 2	Bidder 3	Bidder 4	Bidder 5			
)	54,300 MADE						
	12	1 (800 3					
	Bid Walk A	Attendees					
SIGMA							
JASPER.							
SCHULTE							
	· ·						
This is to certify that bids for the Office located at 600 E. Trade Str	e job identified above were publicly reet, Charlotte, NC.	opened and read aloud I	in the Neighborhood	& Business Services			
Bids Opened By:	from B	olds Recorded By:	why by	h_			
Witnessed By: Date:							
Note: Responsive bids are those which fall within a range of 15% above and 15% below the public body cost estimate. As a general rule, the lowest responsive bid is recommended to the property owner for consideration.							



SAFE HOME

CITY OF CHARLOTTE
NEIGHBORHOOD & BUSINESS SERVICES

Invitation to Bid HNS 19-29

NOTE: Contractors are not authorized to visit the property before or after the bid walk, without being accompanied by the City's Rehabilitation Specialist.

Documents included in Package:

- 1): Instruction to Bidders
- 2) Specs by Location/Trade (Scope of Work)
- 3) Subcontractor Certifications (if applicable) -
- .4) Floor Plan / Site Drawing (if applicable)

Bid Walk & Bid Opening:

Project Address: 853 Belmont Ave.	LEAD SAFE CHARLOTTE TIFICATION REQUIRED FOR LEAD SCOPE OF WORK
Bid Walk: December 6, 2018 @ 10:00 an	
Bid Opening: December 13, 2018 @ 2:00	, , , , , , , , , , , , , , , , , , , ,
Client Name:	Contact Number:
Project Manager: Mike Taylor	Contact Number: 704-336-4115

Bid Walk and Bidding Instructions:

All bid walks are mandatory.

If you are going to be late the policy is the following:

Contact me REFORE the start time if you are going to be late. If you

Contact me BEFORE the start time if you are going to be late. If you are going to be more than 10 minutes late, we will proceed without you and you will not be permitted to bid.

The day of a bid walk the best way to reach me is at Mike Taylor (cell # 980-215-1156).

Bids must be received by the date, time and place specified. All others will be considered non responsive and disqualified.

The Bids will be opened at 600 East Trade St. immediately following the above due date and time.



SAFE HOME

CITY OF CHARLOTTE
NEIGHBORHOOD & BUSINESS SERVICES

Company Acknowledgement: The undersigned, having become thoroughly familiar with the terms, conditions, limitations, and provisions of the housing improvement work to be performed at 853 Belmont Ave to be funded through the City of Charlotte Neighborhood & Business Services, in addition, having fully inspected the site in all particulars, hereby proposes and agrees to fully perform the work within the time stated and in strict accordance with the proposed contract documents including furnishing of any and all labor and materials, and to do all work required to complete said Work in accordance with the advised respective contractual, for the sum of money: All labor, materials, services and equipment necessary for the completion of the Work shown on the Drawings and in the Specifications: Written total 11/5/18 Number of Pages: 3 pages plus 5 page lead scope plus floor plan Specs Dated: Addenda # 1 Dated: . Number of Pages: PAGE W/ HHI line Addenda # 2 Dated: Number of Pages: item was MISSING FROM BID. BASED OF Project Schedule: Minimum Start Date -Completion Deadline: BID PRICE FOR HAL 15 \$1650 Please Print and Sign: Company Name/Firm: **Authorized Representative Name:** Date: Signature:

Work Specification

HH 2--Smoke Detector Hard Wired

HH Building Systems

Install UL approved, interconnected, celling mounted smoke and heat detectors permanently wired into a receptacle boxes with battery backups in bedrooms and outside of sleeping areas.

Detector outside sleeping areas shall be a combination CO/s	moke detector.	•	,	•		
	Bid Cost:		x_	•	_=_	1,600,00
		Base		Quantity		Total Cost
HH 3Water Heater 40 Gallon Electric	•		., ,	HH Plun	nblng	!
Install a 40 gallon, glass lined, high recovery insulated to R-7 pressure and temperature relief valve, expansion tank, dische electric supply. If it is located on an upper floor or if there is rwater heater appropriately.	arge tube to with	in 6" of floo	r or to	outside of st	ructu	re, shut-off valve and
	Bld Cost:		x_		=	1,200,00
		Base		Quantity		Total Cost
HH 4Exterminate insects				· HH Gen	eral F	Requirements
Exterminate for insects. Include a one year warranty. All exte	rmination shall b	e performe	d by a	licensed cor	ntract	or.
	Bld Cost:		х		=	1,000,00
,		Base		Quantity		Total Cost
HH 5GFCI Receptacle 20 AMP	••	14. # . # 1 111111		HH Kitcl	hen	· · ·
Install two flush mounted GFCI duplex receptacles on separa needed.				r. Fish wire	and r	epair all tear out as
	Bld Cost:	Base	^_	Quantity		Total Cost
WIA Cook Born				HH Bath	roon	
HH 6Grab Bars Install 1 1/2" diameter S/S Grab Bars on 3 walls at height of 3 Owners choice of locations.	36" (Include woo	d blocking i	n wall.			
	m		v		_	(000,00
	Bld Cost:	Base	^_	Quantity		Total Cost
See Attached Lead Scope	•••	• • •		General	Requ	ulrements
All work shall be performed in accordance with applicable reg will be obtained as appropriate. Mecklenburg County requires activities subject to permitting under general conducts.	gulations and sha s building permit	all meet all : s for Lead I	applica Hazard	able building i Reduction i	code f the t	s. Building permits work involves
·	Bld Cost:		Х		=	27,450,0
		Base		Quantity		Total Cost
	•		•			
			77	1650)
. Work Specification - City of Charlotte Housing & Neighborhoo	od Services .	· (e		195	Service Servic	11/5/2018 2

Work Specification

Certification

Contractor Name: 50 hults Cm5

Signature:

Total Cost: 34,300,0

Date: 12-10.- 18

LEAD ABATEMENT SCOPE OF WORK

& INSTRUCTIONS TO BIDDERS

853 Belmont Ave.

Complete the following scope of work USING A STATE LICENSED LEAD ABATEMENT CONTRACTOR:

Item# Feature support beams columns (2) around entries boards. support beams and trim entries-wood ceilings, Side A-Unit A and Unit B Side A thru D-wood walls, sidewall and trim and ceiling blue wood entry ceiling conduit Side A-Unit A porch soffits, rafters, and trim corner boards, fascias, Side B and D Back Entries-Side A-Electic panels and boards inculding frames crown moldings, ceiling Method products. Cover with Tyvek and aluminum or vinyl siding MISSING MATERIALS BEFORE COVERING. products. NOTE; REPLACE ROTTED OR Cover with Tyvek and aluminum or vinyl siding Scrape and paint DISCONNECTION AND REPLACEMENT BY SUPPORT FOR THE POST WITH NO GAPS IN wood posts. NOTE: REPAIR FLOOR AND properly. Replace with with 6 x 6 pressure treated Remove existing columns and dispose of OTHERS. Remove and dispose of properly FLOORING AROUND POSTS. FLOOR FRAMING MEMBERS AS NECESSARY TO PROVIDE ADEQUATE STRUCTURAL Number Cost Per unit COST 14,000,00 600,00 50%

10/4/2018

10	φ		7	თ
Sides A through D-paint chips on ground and level	D1 door and door frame	Doors A1, A2, and B1— wood door casings, 8 headers, jambs, and stops	Side D-painted phone and cable wires and accessories	Side C-Attic Vent and Frame
Remove all visible paint chips from the ground. Install landscaping fabric over the soil around the perimeter of the foundation. Fabric shall cover an area 3 feet wide. Install cedar chips 4" deep on top of the landscape fabric. Insure positive drainage away from the foundation.	Remove entire door and frame assembly and dispose of properly. Install a new prehung six panel insulated steel door unit with peephole and keyed leverset and deadbolt keyed alike. INTERIOR AND EXTERIOR CASINGS SHALL MATCH EXISTING. WRAP EXTERIOR CASING.	Remove stops. Cover remaining exterior components with Tyvek and aluminum. Install new stops, primed and painted white. INCLUDES REMOVAL AND REINSTALLATION OF STORM/SCREEN DOORS AS NECESSARY.	Remove and dispose of properly. DISCONNECTION AND REPLACEMENT BY	Remove vent louvers and install a new gable vent. Wrap frame components with aluminum.
,	·			
05C	30° 05%	500°	SQ 18	<u>あ</u> 。999の

ì

Room 9–Unit B bathroom 16 door	Room 7—Unit B front bedroom walls and ceiling.	Room 4—Unit A bathroom	Room 4—Unit A bathroom 13 door	Room 3—Unit A kitchen 12 alcove walls and ceiling	Room 3-Unit A kitchen and alcove-all wooden trim to include baseboard, window components, and door casings, jambs, and stops
Remove all components of existing door assembly and dispose of property. Install a new prehung hollow core lauan door complete with hardware. Casings shall match existing. Paint to match existing.	Scrape loose paint. Repair surface defects to produce a smooth paintable surface. Prime and paint with owner's choice of colors.	Scrape and paint.	Remove all components of existing door assembly and dispose of properly. Install a new prehung hollow core lauan door complete with hardware. Casings shall match existing. Paint to match existing.	Scrape and paint.	d V Scrape and paint.
	·				
500	800	200	300	700	1200.00

•

.

21	20	19	18	17
Room 10—Unit B kitchen and alcove—all painted wooden trim, to include baseboard, window components, and door 21 components.	Room 10-Unit B kitchen and alcove-walls in kitchen and walls and ceiling in alcove	Room 10–Unit B kitchen alcove–Electric panel and conduit	Room 10Unit B kitchen	Room 9–Unit B bathroom– 17 Side D shelving
Remove Door A1 and hinges. Scrape and paint remaining components. Owner's choice of colors.	Remove all cabinets and dispose of property. Cap off sink water and drain lines. Remove miscellaneous cleats from walls. Scrape loose paint. Repair surface-defects to produce a smooth paintable surface. Prime and paint with owner's choice of colors.	Remove painted components and dispose of properly. Terminate wiring in Code approved junction boxes.	Remove loose and damaged plaster back to sound materials. Patch damaged areas to provide a uniform surface. Install 3/8" drywall on the entire ceiling. Finish and sand smooth. Install bed mold around the perimeter of the ceiling. Paint ceiling and bed mold ceiling white.	Scrape and paint.
	,			
	:			
200	1,000	50	600. DE	200,95

.

ļ


22 Entire Property Signature of authorized contractor representative ____ Total Bid: \$ 27,450 undersigned also certifies that the work will be completed within __ Phone: Address: 338 oralist 87 Contractor Submitting Bid: fee in accordance with applicable regulations and the project manual. The The undersigned contractor agrees to perform the scope of work for the indicated 709-20066 stages to minimize relocation time. for details. City will pay for up to two additional HUD lead grant clearance. Most dust wipe Specialized cleaning as necessary to achieve clearances as necessary to schedule work in sample far exceed action levels. Refer to LIRA 120 days of award.



853 Belmont Avenue

Charlotte, NC 28205

SIDE C



SIDE A

Legend

++ = Door

= Window

NOT TO SCALE

SIDE D